











## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Prior to starting work inspect the substrate to ensure that it has been properly prepared to accept materials specified in this Section. Commencement of work shall imply acceptance of surfaces and deck conditions.
  - 1. Review drawings for items such as planters, hot tubs, sculptures or equipment that will be installed on top of wood decking, lumber and timbers. Verify with manufacturer whether additional supports are required.
  - 2. If preparation is the responsibility of another installer, notify Architect in writing of deviations from manufacturer's recommended installation tolerances and conditions.
  - 3. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

- A. Install in accordance with manufacturer's instructions and approved submittals including the following:
  - 1. Install materials plumb, true to line, cut and fitted.
  - 2. Scribe and cope as required for accurate fit to adjacent construction.
  - 3. Use manufacturer's recommended fasteners.
  - 4. Fasten tight to supports. Provide shims if there are variations in framing.

### 3.3 CLEANING AND PROTECTION

- A. Protect from damage during construction operations. Promptly repair any damaged surfaces. Remove and replace work which cannot be satisfactorily repaired.
- B. Clean using materials recommended by the manufacturer to remove stains, dirt and debris prior to final acceptance.

END OF SECTION